MoDOT

105 West Capitol Avenue
P.O. Box 270
Jefferson City, Missouri 65102

Missouri Department of Transportation
Kevin Keith, Director

573.751.2551
Fax: 573.751.6555
1.888.ASK MODOT (275.6636)

ADDENDUM 001
REQUEST FOR BID
Mineola Waste Water Sewer Lagoon Closure Project
Request for Bid 9-120718RJ

Bidders should acknowledge receipt of Addendum 001 (ONE) by **signing** and **including it** with the original bid. The due date for receipt of proposals remains **unchanged** by this Addendum. Accordingly, the following clarifications, questions and answers are believed to be of general interest to all potential Bidders. All other terms and conditions remain unchanged and in full force.

Name and Title of Signer (Print or type)	Name and Title of Department Authority Reva Jones Senior General Services Specialist
Contractor/Offeror Signature (Signature of person authorized to sign)	Department of Transportation Reva Jones (Authorizing Signature)
Date Signed:	Date Signed: July 11, 2012

The following information has been revised by addendum #001:

Per the designer, a complete new set of plans are being provided.

Sheet 2 has been revised to include the Eastbound lagoons.

Per Appendix B – Lagoon Closure Plan – East and West

Erosion Control Plan

II. Waste Water

C. Alternate Method of Disposal

It would be best to not pump into the third cell and instead irrigate the existing water in the cells onto the grass insuring there is no runoff. That would be in compliance with the regulations and an acceptable alternative.

Current lagoon photos as of 7/10/12 are attached.

Section 02200 – Earthwork

1.6 Disposal of Material

C. Vegetative material stripped prior to earthwork commencing shall be removed from the site, or disposed of in accordance with Section 201 of the standard specifications, with the restriction that any open burning will not be permitted at times when smoke might obscure visibility on the highway. If there are burn restrictions, contractor shall remove from site.

Westbound Cell #1

Westbound Cell #2

Westbound Cell #3

Eastbound Cell #1

Eastbound Cell #1

Eastbound Cell #2

Eastbound Cell #3

Eastbound Cell #3

Eastbound Cell #3