



Mark Shelton, District Engineer

ADDENDUM 001
REQUEST FOR BID Installation of Conduit
B10-11326-TB

Bidders should acknowledge receipt of Addendum 001 (ONE) by **signing** and **including it** with the original bid. The due date for receipt of proposals is changed to: **MONDAY, NOVEMBER 22, 2010 at 1:00 PM** by this Addendum. Accordingly, the following clarifications, questions and answers are believed to be of general interest to all potential Bidders. All other terms and conditions remain unchanged and in full force.

Item 1:	The contractor shall supply 2" Orange HDPE Conduit per all applicable requirements of Standard Specification 1060.
Item 2:	The contractor shall be allowed to use a coupler to connect sections of trenched and pushed conduit without a pull box.
Item 3:	The minimum requirement for pull boxes for this contract is to install a pull box at each of the three signal cabinets, on each end of the bridge as directed by the Engineer, and along the conduit run so that there is no more than 1,500 feet between pull-boxes.
Item 4:	<p>Alternative Pull box Layouts for this contract must be pre-approved prior to the bid opening as indicated in the bidding documents. To pre-approve a alternative concept the contractor shall fax or e-mail a sketch of the concept to John Bechtold prior to the bid. This sketch may be a marked-up copy of the Alternate A or B sketches included in the project. After the concept has been reviewed, the contractor will receive a notice via e-mail or fax indicating whether the concept has been pre-approved.</p> <p>For bidding, the contractor shall indicate the updated quantities, unit price and Unit Price Extension in the blank space below the table on the Pricing Page (Page 4) of the bidding documents along with the sketch of the alterative and submit this as part of their bid.</p> <p>John Bechtold Fax #: (573) 243-6281 John Bechtold E-mail: john.bechtold@modot.mo.gov</p>
Item 5:	Only Class 2 Pull boxes are specified for in this contract. Any reference to Class 5 pull boxes is incorrect and should be modified to Class 2.
Item 6:	<p>On the current Pricing Page shows "LF" for the units for the pull boxes. This should be changed to "EACH" for this pay item.</p> <p>For Alternate B, the Pricing Page should show 10 Pull boxes per the drawing instead of 11. This should be corrected on any submittal using Alternate B.</p>
Item 7:	The contractor shall be required to install a #14 Stranded Tracer Wire and a Pull Tape inside the conduit.
Item 8:	For this contract no connection will be required between the new pullboxes and the existing signal cabinets. This will delete the trenching lengths previously shown on the plans between these pull boxes and the cabinets. This will deduct 30 feet from Silver Springs, 15 feet from Broadview and 30 feet at US 61 / Kingshighway.
Item 9:	The contractor shall be responsible for returning any ground disturbed during the operations of the contract to its original condition. This includes seeding and mulching disturbed soil as necessary.

Name and Title of Signer (Print or type)	Name and Title of Department Authority Name Tammy Baker Title Procurement Agent
Contractor/Offeror Signature _____ (Signature of person authorized to sign)	Department of Transportation <i>Tammy L Baker</i> _____ (Authorizing Signature)
Date Signed:	Date Signed: <i>(Insert date signed)</i>