GROVER MAINTENANCE LOT
2639 CENTER STREET, WILDWOOD, MO, 63040

NORTH

LOCATION OF FACILITY

EXHIBIT A - PLANS
SHEET 1 OF 2

Tuesday, Dec 14, 2010 09:40 AM

# GROVER MAINTENANCE LOT
## PLANS & DESCRIPTION OF DEMOLITION WORK

1. METAL STORAGE BUILDING WITH WOOD FRAME ON CONCRETE FOOTINGS WITH DIRT FLOOR
2. USED OIL STORAGE TANK IN CONCRETE CONTAINMENT WITH SHED ROOF
3. CONCRETE BLOCK BUILDING ON CONCRETE SLAB - SEE PAINTED CONCRETE REPORT - ALL CONCRETE BLOCK SHALL BE REMOVED FROM SITE AND DISPOSED AT A LANDFILL
4. METAL STORAGE RACK WITH ROOF
5. LIQUID SALT STORAGE TANKS WITH SPRAY BAR
6. CONCRETE SLAB AND WALLS - FORMER FABRIC SALT STORAGE DOME REMOVED
7. GUARDRAILS ON LOT

NORTH

NOTES: ASPHALT PAVEMENT AND LOT MAY REMAIN IN PLACE.
LEAVE GATE AND POSTS ALONG CENTER AVE. IN PLACE.
ALL REMOVED CONCRETE MAY BE BROKEN UP AND STOCKPILED ON LOT.
COVER ALL EXPOSED SOIL UNDER REMOVED BUILDINGS WITH MINIMUM 2" CRUSHED CONCRETE, ROCK, OR GRAVEL.

EXHIBIT A-PLANS
SHEET 2 OF 2