



NOTE:
CUT PLAN REINFORCING BARS
TO CLEAR PIPE BLOCK-OUT.

NOTE:
CUT PLAN REINFORCING BARS
TO CLEAR PIPE BLOCK-OUT.

NOTE:
DASHED BARS REPRESENT PLAN REINFORCEMENT.
SOLID BARS INDICATE ADDITIONAL #6 BARS.
BAR COVER FROM FACE OF CONCRETE = 1-1/2\"/>

SEE ROAD PLANS FOR LOCATION, SIZE AND
TYPE OF PIPE.
PLACE 5/16\"/>

THE BLOCK-OUT MAY BE ELIMINATED AT
CONTRACTORS ELECTION. IF BLOCK-OUT IS
ELIMINATED, REINFORCEMENT SHALL BE AS
SHOWN EXCEPT PLAN REINFORCEMENT MAY BE
BENT TO CLEAR PIPE.

ADDITIONAL REINFORCEMENT REQUIRED FOR
BLOCK-OUT IS NOT INCLUDED IN ESTIMATED
QUANTITIES. NO SEPARATE PAYMENT WILL BE
MADE FOR ADDITIONAL REINFORCING REQUIRED.

MoDOT MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

THIS MEDIA SHOULD NOT BE CONSIDERED A CERTIFIED DOCUMENT.

CONCRETE BOX STRUCTURE PIPE INLET

DATE EFFECTIVE: 07/01/2001	703.60E	SHEET NO. 1 OF 1
DATE PREPARED: 9/3/2009		

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.