



SECTION 626

RUMBLE STRIPS

626.1 Description. This work shall consist of constructing rumble strips as shown on the plans or as directed by the engineer.

626.2 Construction Requirements. Rumble strips shall be milled into bituminous and concrete pavements to produce a neat and uniform finish. Milled material shall be handled in accordance with [Sec 622](#). Any damage to the pavement or pavement marking resulting from the contractor's operations shall be repaired or replaced to the satisfaction of the engineer by the contractor, at the contractor's expense. On roadways open to traffic, rumble strips shall be in place no later than five days after the final paving operations.

626.3 Method of Measurement. Final measurement will not be made except for authorized changes during construction or where appreciable errors are found in the contract quantity. Where required, rumble strips will be measured separately for each shoulder and the centerline, which will be measured along the centerline of the travel way, and made to the nearest 1/10 station. The revision or correction will be added to or deducted from the contract quantity.

626.4 Basis of Payment. The accepted quantity of rumble strips will be paid at the contract unit price per 1/10 station. Payment will be considered full compensation for all labor, equipment, and material necessary to complete the described work, including loading, hauling, stockpiling and disposal of milled material; and any other incidental items.